Date
 27.01.2019

 Rev
 E

 Author
 E. Hjetland





STAND-ALONE POWER AND COMMUNICATION SUPPLY FOR SUBSEA SYSTEMS



### **BOLT SEA POWER PROGRAM**


**NEXT STEP: PRODUCT DEVELOPMENT** 



- FRED. OLSEN HAS DEVELOPED STAND-ALONE, AUTONOMOUS OFFSHORE POWER GENERATOR TECHNOLOGY SINCE 2007
- TECHNOLOGY DEVELOPMENT COMPLETE ✓
  - RELIABILITY THOROUGHLY VALIDATED AND DEMONSTRATED DURING US NAVY TRIALS 2015-2019

#### **NEXT STEP**

- COMMERCIALLY AVAILABLE PRODUCT:
  - ADAPT DESIGN TO COMMERCIAL PRODUCT AS STAND-ALONE POWER SUPPLY FOR SUBSEA OIL & GAS
  - TO ENABLE DEPLOYMENT OF SUBSEA EQUIPMENT INDEPENDENT OF AVAILABILITY OF POWER AND COMMUNICATION INFRASTRUCTURE
- DEVELOPMENT PROCESS
  - IDENTIFY POTENTIAL CUSTOMERS FOR PRODUCT
  - IDENTIFY PILOT DEMONSTRATION PROJECT PARTNERS
  - IDENTIFY INDUSTRIAL INVESTOR FOR JOINT VENTURE



# FRED. OLSEN GROUP OF BUSINESSES

### 170 YEARS OF INDUSTRIAL EXPERIENCE



#### **SHIPPING:**

CRUISE LINE, TANKERS, SHIP YARDS







#### OIL & GAS:

**EXPLORATION AND PRODUCTION** 







#### **RENEWABLE ENERGY**

ONSHORE WIND FARMS
WIND TURBINE INSTALLATION
VESSELS

WAVE AND TIDAL TECHNOLOGY







### **BOLT SEA POWER**

### AUTONOMOUS, STAND-ALONE POWER UNIT DEVELOPMENT



| 2007    | 2008    | 2009              | 2010 | 2011 | 2012                      | 2013             | 2014  | 2015  | 2016 | 2017 | 2018  | 2019 |
|---------|---------|-------------------|------|------|---------------------------|------------------|-------|---|------|------|---|------|
| BOLT 33 | BOLT 22 | BOLT 1@<br>NORWAY |      |      | BOLT<br>LIFESAVER<br>@ UK | TED ARAS TO MOOR | NG NG | BOLT<br>LIFESAVER<br>@ US NAVY,<br>HAWAII 1 |      |      | BOLT<br>LIFESAVER<br>@ US NAVY,<br>HAWAII 2 |      |

#### SCALE TESTING

- TEST SITE IN NORWAY
- EUROPEAN COMMISSION FUNDED
- TESTING POWER TAKE-OFF PRINCIPLE

#### **FULL SCALE TESTING**

- TEST SITE OUTSIDE FALMOUTH, UK
- UK GOV. FUNDED
- JOINT ENGINEERING WITH SUPACAT LTD.
- TEST FULL SCALE POWER TAKE-OFF DESIGN/

#### **FULL SCALE DEMONSTRATION**

- TEST SITE OUTSIDE HAWAII, USA
- US NAVY FUNDED
- DEMONSTRATE RELIABLE POWER PRODUCTION
- POWER EXPORT TO OBOARD SENSOR PACKAGE
- POWER TRANSPORT SUBSEA


### **LINK TO VIDEO**


FRED. OLSEN LTD. WWW.BOLTSEAPOWER.COM

# **CURRENT TECHNOLOGY**

POWER TAKE-OFF PRINCIPLE

- SIMPLE, ROBUST MECHANICS
- AUTONOMOUS OPERATION
- INTERNET CONNECTION
- ONBOARD ENERGY STORAGE





WAVE ENERGY CONVERTER

**WINCH LINES** 

SUBSURFACE BUOYS

FIBER TETHERS

GRAVITY ANCHORS/ ROCK BOLTS

# **CURRENT TECHNOLOGY**

**BOLT LIFESAVER SYSTEM** 





#### **COMMUNICATION MAST**

- Internet connection
- Radar reflector
- Lightening arrestor

#### **CONTROL HOUSING**

- Controls computer
- Electricals hub
- Long term & short term energy storage
- Client power export system

#### **POWER TAKE OFFs**

- High cycle power take-off winch
- Gear box
- Generator and inverter

#### **CLIENT SYSTEM**

- Ocean sensing equipment package
  - Data processing package

#### **FLOATATION HULL**

- Steel torus
- Low free board for reduced loads


**LINK TO VIDEO** 

### US NAVY DEPLOYMENT

#### **BOLT LIFESAVER OPERATION IN HAWAII**




- 2015-2017 CONTRACT
  - DEMONSTRATE RELIABLE POWER PRODUCTION
- 2017-2019 CONTRACT
  - ACCOMMODATE LARGE OCEAN SENSING PACKAGE AND PROVIDE POWER AND COMMUNICATION



- "...the world's first demonstration of the potentially transformative capability for WECs to enable persistent oceanographic observation and **UUV re-charge** without a cable to shore."
- US Navy press release

### LINK TO VIDEO



### WAVE ENERGY PROGRAM ASSETS TO DATE

**EXPERIENCE AND IP** 




#### OPERATIONAL EXPERIENCE

- 16 YEARS OF UNINTERRUPTED IN-HOUSE DEVELOPMENT
- 5 WAVE ENERGY CONVERTERS BUILT AND OPERATED
- DEPLOYMENT IN 3 COUNTRIES
- 65.000 HOURS AT SEA
- 70+ O&M OPERATIONS
- DEMONSTRATED RELIABLE AND PREDICTABLE POWER PRODUCTION OVER SEVERAL YEARS AT SEA
- REMOTE OPERATION FROM ACROSS THE GLOBE

#### IP AND ASSETS

- 2 KEY PATENTS: HIGH CYCLE WINCH AND LOW MAINTENANCE GEAR BOX (EUROPE, USA, ASIA)
- KEY PERSONNEL WITH 10+ YEARS ON THE PROGRAM STILL TIED TO COMPANY
- OPERATIONAL SOFTWAVE DEVELOPED WITHIN PROGRAM
- FRED. OLSEN CORPORATION STRONG AND DIVERSE MARITIME AND INDUSTRIAL CAPABILITIES

# MEASURED AVERAGE POWER OUTPUT FROM ONE PTO [2012 – 2019]



#### **ENABLER OF REMOTE OPERATION**




- LOCALLY GENERATED POWER AND LIVE INTERNET CONNECTION TO SURFACE AND TO SEABED
  - ENABLES REMOTE OPERATION OF OFFSHORE SYSTEMS
  - ELIMINATES SURFACE VESSELS
  - ELIMINATES RELIANCE ON AVAILABILITY OF POWER AND COMS INFRASTRUCTURE
  - LIVE DATA STREAM FROM AUTONOMOUS SENSORS



- LOW POWER (1-10KW)
- ONE MOORING LINE
- POWER SUPPLY TO SEABED
- COMMUNICATION LINK FROM SEABED TO SHORE
- FAST INSTALLATION AND RECOVERY IN HIGH SEA STATES
- DEEP WATER SITES
- HIGH UPTIME / RELIABILITY
- ROAD TRANSPORTABLE








FRED. OLSEN LTD. 9 WWW.BOLTSEAPOWER.COM

STRENGTH OF FRED. OLSEN TECHNOLOGY



#### WHY WAVE ENERGY FOR STAND-ALONE POWER


- POWER SUPPLY UPTIME
  - WAVES AVAILABILITY VERY HIGH
  - COMBINED WITH ONBOARD STORAGE
  - CAN PROVIDE SUPERIOR CONTINUITY IN POWER SUPPLY
- DENSE ENERGY RESOURCE
  - COMPACT HARDWARE
  - SURVIVABILITY
  - COST EFFICIENT
- RELIABLE UMBILICAL
  - POWER AND COMMUNICATION EMBEDDED IN MOORING LINE
  - MOORING LINE UNDER CONSTANT TENSION CONTROL
  - PROVIDES STIFF AND HIGH RELIABLE LINE
  - AVOIDS SLACK UMBILICAL, FATIGUE WEAR AND SHOCK LOADS



#### SINGLE PTO CONFIGURATION



- FRED. OLSEN TO CONFIGURE EXISTING DESIGNS TO A SMALER UNIT
- STAND-ALONE POWER SUPPLY AND COMMUNICATION PLATFORM FOR SUBSEA OIL & GAS, DEFENCE AND OCEANOGRAPHY MARKET
- PROPOSED PRODUCT
  - SINGLE PTO WINCH
  - 1-10 KW EXPORTED TO SEABED
  - 4G / SATELITE / RADIO LINK
  - ONBOARD BATTERY BANK
  - ONE SINGLE MOORING LINE
  - 3-5M DIAMETER HULL
  - 5-10 DRY TONS (DEPENDING ON SIZE)
  - SPLIT IN ROAD TRANSPORTABLE MODULES




#### PRODUCT DEVELOPMENT PLAN



### **EXISTING DESIGN FOR RE-USE**

- WINCH SYSTEM
  - POWER PRODUCTION
  - STATION KEEPING
- DRIVE TRAIN
  - GEAR BOX
  - GENERATOR & FREQUENCY CONVERTER
- SOFTWARE
  - AUTONOMOUS OPERATION
  - GENERATOR CONTROL
  - LIVE MONITORING
  - DATA ACQUISITION
- POWER MANAGEMENT
  - EXPORT POWER CONVERTION @ 24 700V DC
  - SUBSURFACE POWER EXPORT THROUG WINCH LINE (DRUM TO 15M BELOW SURFACE)
  - BATTERY STORAGE
- COMMUNICATION SURFACE TO SHORE
  - **4**G
  - PEER-TO-PEER RADIO LINK




#### PRODUCT DEVELOPMENT PLAN



### NEW FEATURES REQUIRED FOR

- NEW EXTERNAL STRUCTURE
  - SMALLER, COMPACT HULL
  - TOP COVER
- DEEP WATER MOORING
  - OPERATION AT 500M WATER DEPTH
  - POWER TRANSFER FROM SUB-SURFACE TO SEABED INTEGRATED IN WINCH LINE
  - COMMUNICATION BETWEEN SEABED AND SURFACE INTEGRATED IN WINCH LINE



### **APPLICATIONS**

#### POWER, MONITORING, INSTALLATION



### STAND-ALONE POWER AND COMMUNICATON:

- POWER APPLICATIONS
  - UID DOCKING STATIONS
  - AUTONOMOUS SURFACE VESSEL RECHARGE
  - OFFSHORE FISH FARM
- MONITORING / SENSOR APPLICATIONS
  - WELL HEAD FATIGUE
  - LEAK DETECTION
  - WATER ENVIRONMENTAL MEASUREMENT (TEMP, POLLUTION,...)
  - METOCEAN DATA (WIND AND CURRENT PROFILER, TEMP, HUMIDITY, POLLUTION, WAVE DATA)
  - WATER CURRENT PROFILERS
  - FISH AND MARINE MAMMALS
- INSTALLATION
  - SUPPORT INSTALLATION AND RECOVERY OF SUBSEA EQUIPMENT USING FLOATING STRUCTURE AND WINCH



### SUBSEA OIL & GAS PRODUCT

#### PRODUCT DEVELOPMENT PLAN



#### PILOT DEMONSTRATION PROJECT

- FRED. OLSEN PROPOSES PILOT PROJECT TO DEVELOP PROTOTYPE AND DEMONSTRATE POWER AND COMMUNICATION TO UID DOCK OR SUBSEA SENSOR IN THE FIELD
- IDENTIFY SUBSEA INDUSTRIAL PARTNER WITH SUBSEA SYSTEM FOR DEMONSTRATION OF JOINT SOLUTION

#### PILOT PROJECT TIME LINE:

DEPENDS ON RESOURCING / FINANCING


ENGINEERING: 6 - 12 MONTHS

MANUFACTURING: 3 - 6 MONTHS

VERIFICATION: 3 - 6 MONTHS

FIELD DEMONSTATION: 3 - 6 MONTHS

 TWO YEAR FROM START OF PLANNING TO PROTOTYPE DEMONSTRATION COMPLETED VIABLE PROJECT PLAN





# SUBSEA OIL & GAS PRODUCT




**APPLICATION: UID / AUV DOCKING STATION CHARGE SIMULATION** 

| WEC ONBORD BATTERY           | 100KWH        |  |  |  |
|------------------------------|---------------|--|--|--|
| UID BATTERY                  | 30KWH         |  |  |  |
| MAX CHARGE RATE              | 10KW          |  |  |  |
| UID MISSION DURATION         | 12 HRS        |  |  |  |
| TOTAL DEPLOYMENT<br>DURATION | 4674 HRS      |  |  |  |
| TOAL UID MISSION DELAY       | 484 HRS (10%) |  |  |  |









Fred. Olsen Ltd.

FRED. OLSEN LTD. WWW.BOLTSEAPOWER.COM